

	Quality Electric Inc. Safety Management System		Doc No:	SECTION 23 – TOOLS & EQUIP
			Initial Issue Date	01/01/2022
			Revision Date:	Initial Version
SCAFFOLDS			Revision No.	1
			Next Review Date:	01/01/2023
Preparation: Safety Director	Authority: President	Issuing Dept: Safety	Page:	Page 12 of 12

Tube And Coupler Scaffolds - Light Duty

Uniformly distributed load		Not to exceed 25 p.s.f.
Post Spacing (longitudinal)		10 ft. 0 in.
Post Spacing (transverse)		6 ft. 0 in.
Working Levels	Additional Planked Levels	Maximum Height
1	8	125 ft.
2	4	125 ft.
3	0	91 ft. 0 in.

Tube And Coupler Scaffolds - Medium Duty

Uniformly distributed load		Not to exceed 50 p.s.f
Post spacing (longitudinal)		8 ft. 0 in.
Post spacing (transverse)		6 ft. 0 in.
Working Levels	Additional Planked Levels	Maximum Height
1	6	125 ft.
2	0	78 ft. 0 in.